

# THEMATIC WORKSHOP

## Electrical systems program

Present Status & Business Opportunities



### Jinchao LI

ITER Electrical Systems Program Manager

With 15 years of experience in design, construction, commissioning and operation of Magnetic Confinement Fusion CPSS, Jinchao Li is part of ITER since 2014 and manages the Electrical Systems Program which converts and provides the controlled pulse power to the magnet coils.

The Program also carries out the engineering design of electrical cable trays and cable routing, and provides qualification services of other system equipment working in the tokamak's static magnetic field.



**Chairperson:**

### Max Collins

Business Developer & Project Manager, Big Science Sweden & Lund University  
ILO Sweden





# ITER Electrical Systems: Present Status and Business Opportunities

Jinchao Li




ITER, ESP Program Manager

**Acknowledgement:** Contributions from O. Baulaigue, R. Fan, H. Shen, M. Camuri, M. Tenor, S. Veddemanu, M. Kochergina, etc.

**WEDNESDAY APRIL 25<sup>th</sup>**

Disclaimer: the views and opinions expressed herein do not necessarily reflect those of the ITER Organization





# ITER Electrical Systems: Present Status and Business Opportunities

## 1. ESP Present Status and Achievements

- 1.1 Electrical Power Distribution Systems (PPEN and SSEN)
- 1.2 Ex-Vessel Power Supply System (EV-PSS)
- 1.3 In-Vessel Power Supply System (IV-PSS)
- 1.4 Magnetic Field Compatibility Lab (MFC)

## 2. Companies' Contributions to the ITER Project


RXHK: Driving Innovation in Fusion Technology  
Ampegon AG : Power Electronics

## 3. Collaboration Opportunities in Near Future

- 3.1 Upgrade of PPEN
- 3.2 STATCOM
- 3.3 VS3 power supply
- 3.4 Magnetic Field Compatibility Lab (MFC)







# ESP Present Status and Achievements

- 1.1 Electrical Power Distribution Systems (PPEN and SSEN)
- 1.2 Ex-Vessel Power Supply System (EV-PSS)
- 1.3 In-Vessel Power Supply System (IV-PSS)
- 1.4 Magnetic Field Compatibility Lab (MFC)




150/150 MVA  
0/66/22 kV  
Y/Y/D

No. 3

830 MVA  
(Full installation)

No. 3

110 MVA  
(Full installation)





- Coil power converters
- Radio Freq. and Neutral Beam systems

Includes large Static Var Compensators




# 1.1 Electrical Power Distribution Systems (Present Status)





# 1.2 Ex-Vessel Power Supply System (Configuration)



## Stage 2 Main Coil Power Supply (MCPS)

- 6 CS power converter Units;
- 2 PF power converter Units;
- 4 VS power converter units;
- 10 sets of AC feeding circuits (66 kV);
- 12 sets of DC circuits;
- 3 units of STATCOM (66 kV);
- Cooling water system;
- I&C;
- Others.

The Stage 2 MCPS shall be physically and functionally integrated with the existing ITER system.



## 1.2 Ex-Vessel Power Supply System (Present Status)

### Reactive Power Compensation and Harmonic Filtering (RPC&HF) : Completion of Commissioning and SAT

- The installation and assembly was completed in September 2021.
- The commissioning and Site Acceptance Test (SAT) was completed in November 2024.
- The engineering design, Manufacturing and delivery were contributed by CNDA and its suppliers ( RXPE, etc.).
- The installation and assembly was contracted with Fincantieri & SEAT.
- The installation supervision and commissioning and SAT was contracted with RXPE.
- The RPC&HF system is under pre-operation and maintenance.



Figure 1: Thyristor Control Rectifiers (TCR) in A39



Figure 2: Thyristor Valves (THV) in B38



- ELECTRICAL NOTES of RPC&HF system:
  - Main function: Improve the performance and stability of the PPEN networks by compensating reactive power and eliminating harmonic currents from Coil Power Converters.
  - Total Reactive Power compensated 750 Mvar.
  - Voltage level: 66 kV
  - High voltage insulated cables connecting RPC with PPEN: 72.



# 1.2 Ex-Vessel Power Supply System (Present Status)

Reactive Power Compensation and Harmonic Filtering (RPC&HF) : Completion of Commissioning and SAT

- Component Tests.
- LV & I&C functional Tests
- Interface tests: Full integration with CODAC
- High Voltage Functional Tests: Power-on tests, no-load tests, dynamic performance tests, control performance tests.
- SAT (stand alone system): PSOS automatic tests and 24 h tests





## 1.2 Ex-Vessel Power Supply System (Present Status)

**Ex-Vessel Coil Power Supplies:** the installation and assembly are completed in B32 and 33. Manufacturing, delivery and construction of RFDA equipment are still ongoing.

- The installation and assembly of stage 1 power converters (32 units) was completed by December 2024, the regulatory inspection and corresponding correction are ongoing.
- The manufacturing and delivery of Switch Network Units (SNUs), Fast Discharge Units (FDUs), Protective Make Switches (PMSs) and DC busbar are ongoing. The installation and assembly are ongoing in B11, B74 and B75.


Sub-systems	Da and/or Supplier	Baselined stage of ITER
TF, CS, VS and CC power converters (stage 1)	KODA (PA) and suppliers (Dawonsys, etc.)	SRO
PF power converters (stage 1)	CNDA (PA) and suppliers (ASIPP, etc.)	SRO
RPC&HF System	CNDA (PA) and suppliers (RXPE, etc.)	SRO
SNU, FDU, PMS and DC busbars	RFDA (PA) and suppliers (Efremov Institute, etc.)	SRO
Stage 2 Main Coil Power Converters	Task Agreements with CNDA & KODA (ongoing)	SRO



## 1.2 Ex-Vessel Power Supply System (Present Status)


Ex-Vessel Coil Power Supplies: Low Voltage commissioning started since December 2024 in B32 and B33.

- The low voltage commissioning of power converters are ongoing in B32 and B33, being conducted by ASIPP and Dawonsys.
- The low voltage commissioning of the switches and DC busbar in B32 and B33 will start in 2026.





## 1.3 In-Vessel Power Supply System (Configuration)



- 2x Vertical Stabilization coils
- 27x Edge Localized Mode coils

- The In-Vessel Coils (IVCs) and they consist of 27 ELM coils and a VS3 coil (upper and lower coils connected in series with reverse polarity) .
- The ITER In-Vessel Coils System comprised of the “Edge Localized Mode” (ELM) mitigation coils and the “Vertical Stabilization” (VS3) coils.
- The In-Vessel Coils are located just behind the plasma-facing component and are used to balance the plasma equilibrium with fast magnet feedback controls.
- The main function of the function of the IVC power converters is to receive AC electrical power from the Pulsed Power Electric Network (PPEN) and then provide controlled DC power to the IVC coils to ensure plasma stability through magnetic field control.
- There are:
  - 27 independent power converters for the ELM coils  
**15 kA, 180 V, 4 quadrant operation;**
  - One power converter for the VS coils  
**80 kA (pulse), 2.4 kV, 4 quadrant operation.**



## 1.3 In-Vessel Power Supply System (Configuration)

ELM 27 Inverters  
(in yellow)

ELM Control and  
LV cubicles  
(in brown)

ELM PS DC distribution  
busbars networks

### ELM Tx & Rectifiers



Length:27m  
Width:16m  
Height:8m

### IVC MV SUBSTATION

Length:16m  
Width:6m  
Height:10m

### VS3

Length:35m  
Width:22m  
Height:11m





## 1.3 In-Vessel Power Supply System (ELM-PSS )

- turn-key contract including installation and commissioning
- Electrical ratings
  - Input: 22 kV – 50 Hz
  - Output: **27** individually controlled outputs, 15kA continuously rated, 250 V, with current waveform on the previous slide
  - Load: the table below
- Water cooled, heat dissipation into the building to be minimized
- Background magnetic field: up to 40mT, static or slow changing
- To minimize the size and weight
- Specific seismic, safety and protection requirements


Coil + feeder + VV @ operating temperature	DC mΩ / mH	5Hz mΩ / mH	50Hz mΩ / mH
upper	2.11 / 0.178	3.12 / 0.147	14.0 / 0.0809
Equatorial	2.44 / 0.239	4.01 / 0.169	16.4 / 0.0837
lower	2.57 / 0.197	3.69 / 0.159	14.7 / 0.0885






# 1.3 In-Vessel Power Supply System (ELM-PSS)


ELM dc or ac



ELM ac + RWM ac



ELM ac + EF dc



$$i_{ELM} = I_{ELM} \cos\{n_{ELM}[\Delta\Phi_k - (\Phi_j - \Phi_{ref})] + 2\pi f_{ELM}t\}$$

$$i_{RWM}(t) = I_{RWM} \cos\{[\Delta\varphi_k - (\Phi_j - \Phi_{ref})] + 2\pi f_{RWM}t\}$$

$$i_{EF}(t) = I_{EF} \cos\{n_{EF}[\Delta\varphi_k - (\Phi_j - \Phi_{ref})]\}$$

$f_{ELM}$ : 0 or 1 ~ 5 Hz


$f_{RWM}$ : 5 ~ 50 Hz

$\Delta\Phi_{top} = 66^\circ, \Delta\Phi_{middle} = 0^\circ, \Delta\Phi_{bottom} = 52^\circ$

$\Delta\varphi_{top} = 66^\circ, \Delta\varphi_{middle} = 0^\circ, \Delta\varphi_{bottom} = 52^\circ$

$n_{ELM}=3$  or  $4, n_{EF}=1$  or  $2$

$\Phi_j - \Phi_{ref} = (j-1) \times 40^\circ, j=1, \dots, 9$





## 1.4 Magnetic Field Compatibility Lab (Today Status)

Static Magnetic Field Lab is a Laboratory created in 2023 to test and qualify all materials to be installed in ITER reactor and exposed to Static Magnetic Field.

Our Laboratory, temporarily in B32, is unique in Europe for its technical features, and it is providing:

- Static Magnetic Field to test equipment from 0 to 275mT with stability and linearity of 5% in all axis without limitations
- Coil water cooled and stabilized  $20 \pm 3$  °C for better field stability
- SMF values continuously monitored on 3 axis basis in the range  $\pm 500$ mT
- A testing capacity of 1m<sup>3</sup> and 300Kg in automatic mode and 700Kg in manual mode with a 3-axis load capacity for serial tests on circuit breakers, electric motors, electronics, process valves, relays, etc.
- A complete monitoring and data logging system to record simultaneously up to 108 variables with 1 $\mu$ S/S sampling rate.





## 1.4 Magnetic Field Compatibility Lab (CB Test Bench)

A first advanced expansion available from May 2025 consists of:

- A second testing station dedicated to LV/MV circuit breakers capable to generate from 0 to 50mT (expandable) fully transportable and with pneumatic automation for CBs O-C-O stress and endurance tests under SMF and current.
- Possibility to generate AC test current up to 21.7 kA for intervention or short circuit tests
- Static Magnetic Field with stability and linearity of 5% in all axis without limitations
- A testing capacity of 0.25m<sup>3</sup> and 200Kg in automatic/manual mode with manual load platform for 3 axis objects rotation
- An independent complete monitoring and data logging system to record simultaneously up to 108 process variables with 1μS/S sampling rate and 1TB storage
- SMF values continuously monitored on 1 axis basis in the range ±200mT






## 1.4 Magnetic Field Compatibility Lab ( Motor Test Bench)

A second advanced expansion available from September 2025 will consist of:

- An independent test bench for AC LV asynchronous electric motors tests and qualification up to 25 kW power
- Possibility to run in all 4 quadrants of the working curve (motor/generator)
- Can be associated with the main Coil allowing 0 to 275mT field capacity
- A complete data logging system to record simultaneously up to 108 process variables with 1 $\mu$ S/S sampling rate.







# **2. Companies' contributions to the ITER Project**

Driving Innovation in Fusion Technology (RXHK)

Yao Wu

RXHK, Vice Present



# The year our fusion dream initiated...



<https://www.iter.org/album>

APRIL 2009

AIF-VDC

08 APRIL 2009



THE WORLDWIDE INDUSTRIAL FUSION NETWORK

25/04/2025 20



# Contributions to ITER CPSS stage 1





# Contributions to ITER CPSS stage 2




When ITER Stage-2 and RXHK Generation-2 met


## Readiness and Contribution to ITER CPSS Stage2



ITER VS3 Converter



ITER Stage 2 VSI Converter



ITER MCTB



### IGBT 4.5kV/2kA

- High-Efficiency Power Plant Phase II unit BEST small machine 4Q converter (21MVA)

### IGBT 4.5kV/2kA

- Yu'e BtB HVDC  $\pm 420\text{kV}/1250\text{MW}$
- Patented asymmetrical HB topology
- Achieve domestic leadership



### IGBT 4.5kV/1.5kA

- 25MVA gas pipeline power converter
- Nan'ao HVDC  $\pm 160\text{kV}/200\text{M}$ , World's first offshore multi-terminal VSC-HVDC

### IGBT 1.7kV/1.5kA

- Successful VSC application (SVG)



### IGBT 4.5kV/2kA

- World largest VSC power converter in operation (86MW)

### IGBT 4.5kV/3kA

- WuDongDe Multi-Terminal  $\pm 800\text{kV}/5\text{GW}$
- World's highest voltage and capacity Ultra-HVDC

### IGBT 3.3kV/1.5kA

- 450MW World's first traction power supply to ultra-high-speed Electromagnetic propulsion test facility



### IGBT 4.5kV/5kA

- 8GW HVDC prototype for long distance power transmission Surpassing overseas technology

### IGBT 6.5kV/2kA, 3kA

- 2GW WF HVDC prototype



ITER VS3 & Stage 2 Converter Study

ITER MCTB short delivery

2010

2013

2014

2016

2018

2019

2021

2023

2024




# Where our commitment and passion thrive...



## Four-quadrant high capacity and high current power converter





### ITER In-Vessel Coil Power Supply Topologies Study (IO/21/CT/4300002530)

- Contract signing: Dec, 2021
- Successfully delivered




### ITER Feasibility Study of Stage 2 VSI Converter Units (IO/22/CT/4300002727)

- Contract signing: Oct, 2022
- Successfully delivered



AFE-VSI Solution



LCR-VSI Solution



# Where our commitment and passion thrive...




## Technology Innovation of Power Conversion Advantages – Technical Performance


### ◆ Better Power Quality at Grid Side

Time (s)	Converter Units	Active power(MW)	Reactive power (MVar)	Apparent power(MVA)	Power factor
0.4 *	2 nos of Stage 1 VSI CU in series	-44.8	38.7	59.2	-0.757
	2 nos of Stage 2 VSI CU (AFE-VSI) in series	-46.98	-0.1	49.99	-0.999

Grid voltage under Scenario 1 – Stage 1 VSI




Grid voltage under Scenario 1 – Stage 2 VSI



- ◆ Four-quadrant Operation with Smooth Current Transition at Zero-Crossing
- ◆ Faster Dynamic Response (within 10ms)
- ◆ Reliability of Key Components

No	Power unit	DC voltage	DC current
1	ITER PF	±1050 V	±55 kA
2	ITER CS	±1050 V	±45 kA
3	ITER VSI	±1050 V	±22.5 kA
4	DC-EAF	1000V <sup>a</sup> /1500V <sup>b</sup> DC	> 64kA







# Where our commitment and passion thrive...



## Standalone power supply for TF coil test facility






# Where our commitment and passion thrive...



- ITER - A great premier platform for our technological development and innovation

- Enhancing the proficiency of RXHK Project Management team by exemplary project execution in international Mega-Science initiatives



- Accelerating RXHK's globalization process



AMPEGON



# IBF/25: Power supplies for EC Heating

## Ampegon Power Electronics AG

April 25, 2025 Elvis Dzindo





## **Agenda items**

- 1) Introduction: Ampegon Power Electronics**
- 2) Power supplies for ITER EC heating system**
  - Main High Voltage Power Supplies (MHVPS)**
  - Body Power Supplies (BPS)**
- 3) Learnings from ongoing F4E Contract**
- 4) What is coming next: future developments**
- 5) Global references for EC heating Power Supplies**



## SCIENCE + : FLASH INFORMATION 2024

 **OCem**  
POWER ELECTRONICS

 **ACCELERATOR  
TECHNOLOGIES**

**AMPEGON**

 **PRIATHERM**



**110** People



**50** Mio € Turnover

### Business Unit formed by:

- **OCem Power Electronics**
- **AMPEGON Power Electronics**
- **ACCELERATOR TECHNOLOGIES**
- **PRIATHERM**

### Key points:

- 100 years of experience and know-how in scientific, medical, industrial and transmission technologies;
- Nuclear fusion and accelerator technology;
- Research, innovation, solid states and integrated solutions.




# AMPEGON

Ampegon Power Electronics is a leading player in niche markets for Research Institutions and for Medical/Industrial/Broadcast Applications through technology leadership with:

**High power RF amplifier systems**

**Pulsed power supply applications**


**Shortwave transmitter systems**



- Design, manufacturing and servicing of dedicated RF amplifiers and HV power supplies for Science, Medical, Industrial and Shortwave Broadcast markets
- Subsidiary of Energy Technology s.r.l., Bologna, Italy (A&CT Group)
- Location: Baden (AG), Switzerland (35 employees)



## A Heritage of Excellence





## Our Core Competences

### **RF Expertise:**

Ampegon specializes in RF engineering for single- unit or industrialized production of high power amplifiers

### **Power Electronics:**

Our power electronics provide multi-megawatt outputs with nano-second responses and unrivalled safety

### **Control Systems:**

In-house control development allows use with known standards or custom development as required

### **Industrial Design:**

Bright ideas, clever designs, professionally implemented

### **Tailor Made Solutions:**


Ampegon applies decades of expertise to the requirements of your business.



«Our devoted R&D teams are proud to develop systems for science and research. Ampegon technology is top of the line and our solutions for this highly challenging field are esteemed by customers all over the globe.» Franz Arnold, Business Development R&D



# Pulse Step Modulator (PSM) Technology



Advantages:






High efficiency >97%

Flexible waveforms, CW output

Limitations:

Overshoot possible

Pulse ripple (module switching)





## 2) EC Power Supplies for ITER

### Cathode Power Supply (MHVPS)

- ✓ 55kV / 110A CW
- ✓ 2 Gyrotrons (55kV, 55A, 170GHz) per MHVPS
- ✓ On-Off Modulation:  $\leq 5\text{kHz}$
- ✓ Arc Limitation System (ALS)
- ✓ Efficiency:  $\geq 97\%$

### Project status

- All 8 units delivered between 2018 - 2021
- Site installation is completed
- Commissioning works ongoing
- Site works completion: expected within 2026/27





## 2) EC Power Supplies for ITER

### Body Power Supply (BPS)

- ✓ 35kV / 100mA
- ✓ 1 BPS per Gyrotron
- ✓ On-Off Modulation  $\leq 5\text{kHz}$



### Project Status

- All 16 units delivered between 2018-2021
- Site installation works are completed
- Commissioning work is ongoing
- Site works completion: expected within 2026/27





## 2) EC Power Supplies: Site layout





# 3.

## Collaboration Opportunities in Near Future

- 3.1 Upgrade of PPEN
- 3.2 STATCOM
- 3.3 VS3 Power Supply (VS3-PS)
- 3.4 Magnetic Field Compatibility Lab (MFC)



## 3.1 Upgrade of PPEN

The PPEN upgrade activities concern the **procurement, installation and commissioning** of the following Work packages:

- PPEN AC distribution for Ex-Vessel **Magnet Power Converter stage 2** (10 circuits)  
✓ 12km of 66kV cables - 240mm<sup>2</sup> & 300mm<sup>2</sup>
- PPEN AC distribution for **In-Vessel Coil Power Supplies** (VS3 and ELMs feeders)  
✓ 8 km of 22kV cables - 185mm<sup>2</sup>
- PPEN AC distribution for **ICH & ECH – SRO**  
✓ 10 km of 22kV cables - 150mm<sup>2</sup> & 240mm<sup>2</sup>
- PPEN AC distribution for **ICH & ECH – DT1**  
✓ 28 km Cables 22kV/ (GIS – TBC) 22kV Switchgear 13 feeders - 150mm<sup>2</sup> & 240mm<sup>2</sup> & 400mm<sup>2</sup>

PPEN AC Distribution for MCPC stage 2																				
Activities	2026				2027				2028				2029				2030			
	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
Design and Manufacturing																				
Installation and Commissioning																				


PPEN AC Distribution for IVC Power supplies																				
Activities	2026				2027				2028				2029				2030			
	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
Design and Manufacturing																				
Installation and Commissioning																				

PPEN AC Distribution for ECH & ICH - SRO																				
Activities	2026				2027				2028				2029				2030			
	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
Design and Manufacturing																				
Installation and Commissioning																				

PPEN AC Distribution for ECH & ICH - DT1																				
Activities	2026				2027				2028				2029				2030			
	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
Design and Manufacturing																				
Installation and Commissioning																				



### 3.1 Upgrade of PPEN






## 3.2 STATCOM

- Stage1 RPC uses SVC (Static Var Compensator) configuration which is mainly controlled by Thyristors.
- STATCOM will be used to integrate with the stage1 RPC system.
- STATCOMs will be designed to integrate with the stage1 RPC system
  - ✓ It Compensates the remaining exceeding reactive power.
  - ✓ It Compensates the remaining harmonics leftover by stage1 RPC system.
  - ✓ It also compensates the slower time response of the stage1 RPC and to mitigate the overvoltage during fast transients such as load rejection.
- STATCOM is expected to connect at 66 kV bus, with or without step-up transformer.

**Rating:** 3x90 MVar (Tentative)

**Connection:** 66 kV level


**Control Switch:** IGBT



STATCOM for Bus 1



### 3.3 VS3 Power Supply



$$I = I_{vde} + I_{noise}$$

$$I_{vde} = A \left( \epsilon^{-t/\tau_1} - \epsilon^{-t/\tau_2} \right)$$

$$I_{noise} = I_{noise\_rms} \sqrt{2} \sin(2\pi ft)$$

$$A = 99200 \text{ A}$$

$$\tau_1 = 0.304 \text{ sec}$$

$$\tau_2 = 0.016 \text{ sec}$$

$$I_{noise\_rms} = 2907 \text{ A}$$

$$f = 30 \text{ Hz}$$

- turn-key contract including installation and commissioning
- Charging power (10s) : 3.5 MW
- Output peak power: 192 MW for 0.3s
- Output peak current:  $\pm 80 \text{ kA}$  for 0.3s
- Output current (continuous, rms): 4 kA
- Output voltage :  $\pm 2.4 \text{ kV}_{dc}$
- Energy bank : 25 MJ





Coil + feeder + VV @ operating temperature	DC mΩ / mH	30Hz mΩ / mH
Upper 4 turns + lower 4 turns	14.0 / 1.33	49.7 / 0.493




## 3.3 VS3 Power Supply


- One **upper** and one **lower 4-turn** “ring” coil connected in an anti-series;
- Control the **vertical position of the plasma**;

### Possible operation modes

NORMAL OPERATION	DIAGNOSTIC SENSORS CALIBRATION ACTIVITIES		
	Antie-series	Upper singly	Lower singly
			
			



VS Upper coil : 4 Turns





VS Lower coil : 4 Turns



## 3.4 Magnetic Field Compatibility Lab (New Building)

For the activity future expansion and new business development, a bigger and new location has been designed, and a dedicated International Tender for the construction of a 2000 m<sup>2</sup> internal surface will be launched for civil works and technological installations.

The expected realization time is 12 months, herewith below described the preliminary layout.





## 3.4 Magnetic Field Compatibility Lab (MFC Service Provider)

Our activity is in strong expansion, aiming to reach 100% of the testing capacity from middle 2025 on producing high quality tests within the three product lines:

- **Static Magnetic Field (SMF) Main Test Facility**
- **Circuit Breaker (CB) Test Bench**
- **Electrical Motor Test Bench**

*Our laboratory started the process of COFRAC accreditation which we aim to achieve Q1 2026. It is the highest level of accreditation in France according ISO 17025 STD.*



*“Thanks to our earned experience, the continuous quality control on all test process, the accreditation, we will be soon in condition to fulfil not only the IO internal demand (IO-DAs), but also all requests coming from external customers (third parties) willing to test and qualify their products for the Fusion global market”*





# THANKS

TO BE PART OF THE WORLDWIDE **FUSION** NETWORK



PLATINIUM SPONSOR



SILVER SPONSOR



SILVER SPONSOR



BRONZE SPONSOR

